

**BOQ for repair of stern unit and annual maintenance of S.L.Kosi during the year 2011-12**

**L- 21.5 M, B - 5.82M, Draft - 0.8 M, GRT - 63.58.**

SL. NO	DESCRIPTION OF WORK	UNIT	QTY	RATE	AMOUNT
1	Both side propeller, propeller shaft and it bushes is to be opened for finding out the clearness & checking of trueness, buildup of bushes, etc and rectified in OE position as per drawing after fairing with same composition of Material / renewed the bushes				
(a)	Labour charge	No.	2		
(b)	Machining charge (actual + 10 % basis if required)	LS			
(c)	Cost of spare (actual + 10 % basis if required)	LS			
2	Both rudder assembly to be dismantled, rudder stock, shaft, bushes etc to be checked and if required same to be build up as per OE size (as per drawing) and fitted back in position				
(a)	Labour charge	No.	2		
(b)	Machining charge (actual + 10 % basis if required)	LS			
(c)	Cost of spare (actual + 10 % basis if required)	LS			
3	Fire extinguisher to be serviced refilled and tested				
(a)	Foam type - 9 lts	No.	4		
(b)	Dry Powder - 5 Kgs	No.	5		
(c)	Soda type - 9 Lts	No.	2		
4	G.S.Pump is to be serviced.				
a	Labour charge	No.	1		
b	Cost of spare (actual + 10 % basis if required)	LS			
5	Beaching, Mooring, Dock hire charges for completion of above works.	Complete	Complete		
	Total Amount (in Rs. )				